BID SUMMARY

This document is a summary of bids received for the subject project and are provided only as a convenience. Listing of a particular bid is not a finding that such bid has been found to be responsive or accepted as complete by the City. An award of contract, if any, is subject to approval of the City Council and/or the City Manager. Contractors should refer to the contract documents for bidding information.

PROJECT TITLE: **Annual Sidewalk Repair Program 2013-14**
PROJECT NO.: **2014.006**
BID NO.: **13-14.007**

BID OPENING	**ENGINEER'S ESTIMATE**	Rosas Brothers Construction	JJR Construction, Inc.	Sposeto Engineering, Inc.
DATE: Wednesday, October 23, 2013	Date Approved: **10/9/2013**	4731 Colliseum Way	1120 Ninth Avenue	4558 Contractors Place
TIME: 3:00 p.m.	Prepared by: **A. Osakwe**	Oakland, CA 94601	San Mateo, CA 94402	Livermore, CA 94551
LOCATION: City Clerk's Office		Phone: (510) 534-1077	Phone: (650) 343-6109	Phone: (925) 443-4200
		Fax: (510) 534-5077	Fax: (650) 343-6207	Fax: (925) 443-5800

ITEM NO.	ITEM	QUANTITY	UNIT COST	ITEM COST	UNIT COST	ITEM COST	UNIT COST	ITEM COST	UNIT COST	ITEM COST
1	Install curb and gutter per drawing 100 case 3101	1200 LF	$45.00	$54,000.00	$48.00	$57,600.00	$80.00	$96,000.00	$96.00	$115,200.00
2	Install sidewalk per drawing 100 case 3101	8000 SF	$12.00	$96,000.00	$10.25	$82,000.00	$13.00	$104,000.00	$16.00	$128,000.00
3	Install 6" driveway per drawing 102 or drawing 110 case 3101	2500 SF	$13.00	$32,500.00	$12.00	$30,000.00	$19.00	$47,500.00	$16.00	$40,000.00
4	Install 8" driveway per drawing 102 or drawing 110 case 3101	600 SF	$16.00	$9,600.00	$14.25	$8,550.00	$24.00	$14,400.00	$17.00	$10,200.00
5	Install wheelchair curb cut ramp per drawing 106A and B case 3101	5400 SF	$18.00	$97,200.00	$13.75	$74,250.00	$21.00	$113,400.00	$23.00	$124,200.00
6	Install depressed driveway approach per drawing 108 case 3101	180 SF	$16.00	$2,880.00	$14.00	$2,520.00	$19.00	$3,420.00	$24.00	$4,320.00
7	Install basket weave sidewalk per drawing 112 case 3101	300 SF	$14.00	$4,200.00	$14.00	$4,200.00	$19.00	$5,700.00	$45.00	$13,500.00
8	Install valley gutter per drawing 114 case 3101	240 SF	$22.00	$5,280.00	$16.00	$3,840.00	$24.00	$5,760.00	$28.00	$6,720.00
9	Install stamped concrete paving per drawing 116 case 3101	100 SF	$21.00	$2,100.00	$16.00	$1,600.00	$35.00	$3,500.00	$40.00	$4,000.00
10	Install tack on curb per drawing 118 case 3101	50 LF	$32.00	$1,600.00	$30.00	$1,500.00	$30.00	$1,500.00	$32.00	$1,600.00
11	Install vertical curb per drawing 118 case 3101	50 LF	$40.00	$2,000.00	$40.00	$2,000.00	$80.00	$4,000.00	$75.00	$3,750.00
12	Grind raised concrete sidewalk to flush with adjacent grade, within 48 hrs of notification	100 LF	$2.50	$250.00	$16.00	$1,600.00	$100.00	$10,000.00	$29.00	$2,900.00

BID SUMMARY

This document is a summary of bids received for the subject project and are provided only as a convenience. Listing of a particular bid is not a finding that such bid has been found to be responsive or accepted as complete by the City. An award of contract, if any, is subject to approval of the City Council and/or the City Manager. Contractors should refer to the contract documents for bidding information.

PROJECT TITLE: **Annual Sidewalk Repair Program 2013-14**
PROJECT NO.: **2014.006**
BID NO.: **13-14.007**

BID OPENING	**ENGINEER'S ESTIMATE**	Rosas Brothers Construction	JJR Construction, Inc.	Sposeto Engineering, Inc.
DATE: Wednesday, October 23, 2013	Date Approved: **10/9/2013**	4731 Colliseum Way	1120 Ninth Avenue	4558 Contractors Place
TIME: 3:00 p.m.	Prepared by: **A. Osakwe**	Oakland, CA 94601	San Mateo, CA 94402	Livermore, CA 94551
LOCATION: City Clerk's Office		Phone: (510) 534-1077	Phone: (650) 343-6109	Phone: (925) 443-4200
		Fax: (510) 534-5077	Fax: (650) 343-6207	Fax: (925) 443-5800

ITEM NO.	ITEM	QUANTITY	UNIT COST	ITEM COST	UNIT COST	ITEM COST	UNIT COST	ITEM COST	UNIT COST	ITEM COST
13	Install cast iron pipe curb drain per drawing 212 case 3101	40 LF	$24.00	$960.00	$20.00	$800.00	$75.00	$3,000.00	$30.00	$1,200.00
14	Remove and reset pavers at existing tree per drawing 436 case 3101	400 SF	$18.50	$7,400.00	$10.00	$4,000.00	$25.00	$10,000.00	$60.00	$24,000.00
15	Install retrofit frame for tree grate in existing concrete per drawing 438A and B case 3101	1 EA	$1,750.00	$1,750.00	$1,150.00	$1,150.00	$1,000.00	$1,000.00	$8,000.00	$8,000.00
16	Install cast in place frame for tree grate per drawing 438A and B case 3101. Including all steel but excluding concrete	2 EA	$1,500.00	$3,000.00	$1,500.00	$3,000.00	$1,000.00	$2,000.00	$8,000.00	$16,000.00
17	Install cast iron tree grate per drawing 438A and B case 3101	2 EA	$1,500.00	$3,000.00	$900.00	$1,800.00	$1,000.00	$2,000.00	$8,000.00	$16,000.00
18	Remove 4" Concrete and backfill with topsoil	300 SF	$8.00	$2,400.00	$4.00	$1,200.00	$10.00	$3,000.00	$13.00	$3,900.00
19	Provide traffic control plan and implement traffic control per section 7-10.3.3 and 7-10.3.4 with a flashing arrow panel	2 Plans	$2,150.00	$4,300.00	$350.00	$700.00	$2,000.00	$4,000.00	$10,000.00	$20,000.00
20	Provide traffic control plan and implement traffic control per section 7-10.3.3 and 7-10.3.4 without a flashing arrow panel	2 Plans	$1,750.00	$3,500.00	$300.00	$600.00	$2,000.00	$4,000.00	$10,000.00	$20,000.00
21	Remove existing pavers, trim roots, and install decomposed granite at existing tree well	4 EA	$650.00	$2,600.00	$350.00	$1,400.00	$1,000.00	$4,000.00	$600.00	$2,400.00
22	Install decomposed granite at empty tree well	4 EA	$400.00	$1,600.00	$200.00	$800.00	$1,000.00	$4,000.00	$400.00	$1,600.00

BID SUMMARY

This document is a summary of bids received for the subject project and are provided only as a convenience. Listing of a particular bid is not a finding that such bid has been found to be responsive or accepted as complete by the City. An award of contract, if any, is subject to approval of the City Council and/or the City Manager. Contractors should refer to the contract documents for bidding information.

PROJECT TITLE: **Annual Sidewalk Repair Program 2013-14**
PROJECT NO.: **2014.006**
BID NO.: **13-14.007**

BID OPENING **DATE:** Wednesday, October 23, 2013 **TIME:** 3:00 p.m. **LOCATION:** City Clerk's Office			**ENGINEER'S ESTIMATE** Date Approved: **10/9/2013** Prepared by: **A. Osakwe**		Rosas Brothers Construction 4731 Colliseum Way Oakland, CA 94601 Phone: (510) 534-1077 Fax: (510) 534-5077		JJR Construction, Inc. 1120 Ninth Avenue San Mateo, CA 94402 Phone: (650) 343-6109 Fax: (650) 343-6207		Sposeto Engineering, Inc. 4558 Contractors Place Livermore, CA 94551 Phone: (925) 443-4200 Fax: (925) 443-5800	
ITEM NO.	**ITEM**	**QUANTITY**	**UNIT COST**	**ITEM COST**	**UNIT COST**	**ITEM COST**	**UNIT COST**	**ITEM COST**	**UNIT COST**	**ITEM COST**
23	Remove and replace 2' x 2' of temporary AC patch to allow compaction testing by others	30 EA	$300.00	$9,000.00	$100.00	$3,000.00	$1,000.00	$30,000.00	$150.00	$4,500.00
24	Compact existing base at roadway excavation per section 301-2.	375 SF	$11.50	$4,312.50	$5.00	$1,875.00	$10.00	$3,750.00	$10.00	$3,750.00
25	Excavation resurfacing per drawing 122A, B, C case 3101: 6" thickness	500 SF	$12.50	$6,250.00	$9.00	$4,500.00	$16.00	$8,000.00	$16.00	$8,000.00
26	Excavation resurfacing per drawing 122A, B, C case 3101: 9" thickness	125 SF	$15.00	$0.00	$13.00	$1,625.00	$25.00	$3,125.00	$18.00	$2,250.00
27	Excavation resurfacing per drawing 122A, B, C case 3101:12" thickness	125 SF	$17.00	$2,125.00	$15.00	$1,875.00	$35.00	$4,375.00	$24.00	$3,000.00
		TOTAL BASE BID:		**$359,807.50**		**$297,985.00**		**$495,430.00**		**$588,990.00**
		SUBCONTRACTORS:			Bay Line		Del Secco Saw & Core D & S Trucking		None	
		SECURITIES:			10% Bid Bond		10% Bid Bond		10% Bid Bond	
		NOTES:								

Reviewed by: _____ **Date:** 10/24/13
Austine Osakwe, Project Manager

Reviewed by: _____ **Date:** 10/24/13
Ken Joseph, City Engineer