


- NOTES:**
- All work shall be done in accordance with the Standard Specifications for Public Works Construction, the "GREENBOOK", the most current edition and all supplements thereto, adopted by the Southern California Chapter of the American Public Works Association and the Special Provisions (Technical Specifications) thereto adopted by the City.
 - Field conditions (electroliner, utility boxes, trees, etc.) shall determine size and spacing of panels - City Engineer approval of layout is required.
 - General Concrete Notes Dwg. 104 Case 3101 shall apply.
 - See Dwg. 100, 102, Case 3101 for curb, gutter, sidewalk and driveway details.
 - Patterned sidewalk requires four separate pours:
 - Curb and gutter (medium broom finish)
 - 300mm(12") strips (medium broom finish)
 - Longitudinally broomed panels (coarse broom finish)
 - Transversely broomed panels (coarse broom finish)
 (Burke Keyed Cold Joints or approved equal may be substituted for cold joints)
 - Concrete shall contain 1.8kg(4 lbs.) lampblack per cubic yard unless otherwise directed by the City Engineer.

ACAD FILE NO. C3101D112.DWG.

CITY OF SAN LEANDRO * STANDARD PLANS

NO.	REVISIONS	DATE	BASKET WEAVE PATTERNED SIDEWALK			APPROVED							
						 Kenneth Joseph, City Engineer R.C.E. No. 34870 Expires 9/30/03							
DRAWN	GF/MLWH/VL	CHECKED	KJ/KRC	DATE	May 2002	SCALE	NONE	SHEET	1 OF 1	DWG. NO.	112	CASE.	3101