

05/01/2001

BID NO. 00-01.032 SOUTH OFFICES INTERIOR RENOVATION PROJECT

The bid package for this project is hereby amended as follows:

Sheet A-2

CLARIFICATION: Delete the ramp outside the Lobby 101...bevel sown the concrete inside the new Door No. 1 from a distance of 18" back away from the door.

CLARIFICATION: The large work area to be designated Room Nos. 107, 108, 112 and 11? currently have fabric wall covering on the South and West walls. Apply ½" gypsum wallboard over the top, attach with drywall screws at 6" o.c., tape, texture and paint. Make sure to project all electrical outlets that are presently in the wall.

CLARIFICATION: Doors to Room Nos. 109 and 110 will be removed and replaced with metal frames and 3'-0" x 7'-0" doors.

CLARIFICATION: On the Finish Schedule the notation (e) indicates that the material finish is existing and the (o) indicates the finish.

SIGN AND RETURN INSIDE SEALED BID

Bidder signature

Darryl Sweet
Purchasing Supervisor